

3/4/09

Pete Messa
(408) 4381016

Brush Rd. Association —

The Add Items for Storm Drain Installation along Brush Rd does not include asphalt repair. Please see South Bay Paving Proposal which I have included herein. It includes (2) paving options:

- 1) patch pave along south edge of road @ location of proposed storm drain installation or
- 2) overlay entire road in this vicinity from gate pillars to upper end of storm drain (630 ft).

Pete

Add Item: Storm Drain Installation along Brush Rd.

1. Install Storm Drain System as described herein: Trench, install, backfill 650 Lineal feet of 18" diameter HDPE pipe placed with 2 ft minimum cover to finish street grade; Install (4) concrete drain boxes 2ft by 2ft with traffic grate inlets; connect to existing

page 2 of 3

drainage pipes at uphill, middle and downhill ends of new improvements. Work must be done in conjunction with Brush Rd. Culvert Repair. Does not include asphalt patchwork or street overlay. See South Bay Paving Bid Proposal.

ITEM COST: \$40,925.00

EXCLUSIONS:

- 1) All required engineering, design, consultation, mat'l testing, survey and staking.
- 2) Cost and provision of any required site specific permits, right of ways, inspections, and material tests, unless otherwise noted herein.
- 3) All costs relating to the discovery of contaminated materials or toxins on this project site.
- 4) Installation, relocation, and/or removal of utilities and undisclosed underground objects such as tanks and utilities.
- 5) Cost for Bonding, if required.
- 6) Protective fencing, if required, unless otherwise noted herein.
- 7) Erosion control measures such as seeding, mulching, netting, silt fencing, etc., unless otherwise noted herein.
- 8) Sub-excavation below lines and grades shown on plans. No Soils Report was provided.

THANK YOU FOR THE OPPORTUNITY TO PROVIDE INPUT ON THIS PROJECT. IF YOU HAVE ANY QUESTIONS REGARDING THIS BID AND PROPOSAL, PLEASE CONTACT ME AT (831) 476-8221. PAYMENT TERMS: PROGRESS PAYMENTS DUE MONTHLY AND/OR ANY UNPAID BALANCE DUE UPON SATISFACTORY COMPLETION OF SCOPE OF WORK. CONTRACT PROVIDED UPON REQUEST.

Sincerely,



**PETER G. MESSA, PRESIDENT
PETE MESSA & SONS, INC.**

ACCEPTANCE OF TERMS OF THIS PROPOSAL:

BY:

PRINT NAME:

TITLE:

DATE:

Southbay Paving
315 Penn Way
Los Gatos, CA 95032
Lic # C-12 402822
408.656.4442 Cell
408.353.8944 Fax

March 3, 2009

Mr. Pete Messa
Messa & Sons Inc.
26690 Soquel-San Jose Road
Los Gatos, CA 95033-9249

Re: Paving Repairs for Brush Road

Dear Pete:

Thank you for giving us this opportunity to bid your work. Should you have any questions please feel free to call me at anytime convenient to you at 408.656.4442.

Item A – Asphalt Pavement of Driveway Approximately 12,800 Square Feet

1. Clean existing asphalt surface using power blowers.
2. Apply a binder coat of oil to the existing asphalt surface.
3. Buy, haul, place, and compact three inches in thickness, of 1/2" medium grade asphalt.
4. Seal new asphalt with ss-1h cut 50% with water.

ALL OF THE ABOVE WORK IN ITEM A INCLUDING EQUIPMENT, LABOR AND MATERIALS, IS PERFORMED FOR THE SUM OF:

Two Inches of Asphalt \$25,601.00
Three Inches of Asphalt \$34,556.00

Item B – Four Inch Asphalt Pavement Repairs : Totaling 2,840 Sq. Ft. of Four Inch

1. Tackcoat the excavated edges with SS-1H oil.
2. Install 4" of hot asphalt plant mix, 1/2" medium grade two lifts.
3. Roll to maximum compaction.
4. Seal new asphalt surface with SS-1h oil cut 50%.

**ALL OF THE ABOVE WORK IN ITEM B, INCLUDING EQUIPMENT,
LABOR AND MATERIALS, IS PERFORMED FOR THE SUM OF: \$12,292.00**

- This price is good for thirty calendar days.
- Southbay Paving cannot be held responsible for work done by others.
- Bonds, permits, import of engineered fill to site, demolition, professional engineering, soils testing, fees, permits, off-site improvements to Brush Road, headerboards, horse/walking/jogging paths, striping, or any damage to underground utilities are not included in this proposal.
- Please note that if the existing subgrade is wet and unstable due to rainfall or natural conditions, the additional work necessary to stabilize the subgrade will be an additional charge negotiated on site by SOUTHBAY's representative.
- Terms: 100% of contract due and payable upon completion of each item or a 1 1/2% finance charge will be assessed on the unpaid balance.

Sincerely,

A. F. Sturla

PROPOSAL AND CONTRACT ACCEPTED BY _____ DATE _____